SPECIAL CONDITIONS OF CONTRACT

Construction of RCC Boxes for RUB Work

1. **Scope of Work:** The scope of the contractor under this contract shall be strictly limited to excavation, preparation and construction of the thrust bed and casting of two (2 Nos.) RCC barrel units in front of the railway embankment, as per the approved General Arrangement Drawing (GAD) and structural drawings.
2. **Excavation:** The contractor shall carry out excavation to the required dimensions and levels for construction of the thrust bed and casting of the RCC box units, as per the approved drawings and instructions of the Engineer-in-Charge.
3. **Construction of Thrust Bed:** The contractor shall construct the required thrust bed with specified concrete grade, reinforcement and dimensions as per the approved structural drawings. The thrust bed shall be properly aligned and levelled to facilitate subsequent box-pushing operations by the other agency.
4. **Casting of RCC Boxes:** The contractor shall construct and complete two (2 Nos.) RCC box barrels at the designated location in front of the railway embankment, strictly in accordance with the approved drawings, specifications and quality requirements. The RCC boxes shall be completed in all respects and made ready for subsequent pushing operations.
5. **Exclusion of Box-Pushing Work:** The actual pushing of RCC box units beneath the railway track, including hydraulic jacking, installation of pushing arrangements, cutting of embankment, removal of soil during pushing and associated operations, shall NOT form part of this contract. These activities shall be carried out by another agency under a separate sanctioned estimate.
6. **Coordination with Other Agency:** The contractor shall complete the RCC box casting and thrust bed works in such a manner as to facilitate the subsequent box-pushing operation by the other agency. The contractor shall coordinate with the Engineer-in-Charge regarding the completion and handing over of the completed RCC boxes and thrust bed.
7. **Quality and Specifications:** All works shall be executed in accordance with the approved GAD, structural drawings, relevant IRS specifications, Railway codes and instructions issued by the Engineer-in-Charge.
8. **Safety:** The contractor shall take all necessary precautions during excavation, thrust bed construction and RCC box casting to ensure the safety of railway assets, railway embankment, workers and the general public.
9. **Clear Demarcation of Scope:** No payment or claim shall be admissible under this contract towards box-pushing operations or any other activities specifically excluded from the above scope and entrusted to the other agency under a separate sanctioned estimate.

Signature Not Verified
Digitally signed by ROLLAKUPPASWAMY KISHORE
Date: 2026.11.10 18:40:54 IST
Reason: IREPS-CRIS
Location: New Delhi