DRM/Engineering acting for and on behalf of The President of India invites E-Tenders against Tender No **17-Sr-DEN-VI-LKO-2026-27** Closing Date/Time 21/12/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Annual repairs, white washing, painting, drain of various colonies & roads in the section of SSE/Works/PRG under ADEN/PRG in the jurisdiction of Sr.DEN-VI/LKO.		
Bidding type	Normal Tender		
Tender Type	Open	**Bidding System**	Single Packet System
Tender Closing Date Time	21/12/2026 15:00	**Date Time Of Uploading Tender**	27/11/2026 16:10
Pre-Bid Conference Required	No	**Pre-Bid Conference Date Time**	Not Applicable
Advertised Value	9999981.41	**Tendering Section**	ON PRG
Bidding Style	Single Rate for Each Schedule	**Bidding Unit**	
Earnest Money (Rs.)	200000.00	**Validity of Offer (Days)**	60
Tender Doc. Cost (Rs.)	0.00	**Period of Completion**	12 Months
Contract Type	Works - General	**Contract Category**	Expenditure
Bidding Start Date	07/12/2026		
Are JV allowed to bid	No	**Number of JV Member Allowed**	0
Are Consortium allowed to bid	No	**Number of Consortium Member Allowed**	0
Ranking Order For Bids	Lowest to Highest	**Expenditure Type**	Revenue
Zonal Contract	No	**Bids to be obtained**	Inclusive of GST
Composite Tender	No	**PVC Applicable**	No

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule 01 - All DSR ITEMS-2021 (Inclusive all taxes and GST @ 18%)							9999981.41	Above/ Below/Par
01	Please see Item Breakup for details.				505000.00	(-) 11.54	446723.00	
	Description:- SH: 0.1 HIRE CHARGES OF PLANTS & MACHINERY							
02	Please see Item Breakup for details.				1142730.00	(-) 11.54	1010858.96	
	Description:- SH: 0.2 LABOUR							
03	Please see Item Breakup for details.				701935.00	(-) 11.54	620931.70	
	Description:- SH: 0.3 MATERIALS							
04	Please see Item Breakup for details.				68334.00	(-) 11.54	60448.26	
	Description:- SH: 4.0 CONCRETE WORK							
05	Please see Item Breakup for details.				188267.00	(-) 11.54	166540.99	
	Description:- SH: 5.0 REINFORCED CEMENT CONCRETE							
06	Please see Item Breakup for details.				813223.25	(-) 11.54	719377.29	
	Description:- SH: 6.0 MASONRY WORK							
07	Please see Item Breakup for details.				85076.00	(-) 11.54	75258.23	
	Description:- SH:8.0 CLADDING WORK							
08	Please see Item Breakup for details.				791488.00	(-) 11.54	700150.28	
	Description:- SH: 9.0 WOOD AND P.V.C. WORK							
09	Please see Item Breakup for details.				671700.00	(-) 11.54	594185.82	
	Description:- SH 10: STEEL WORK							
10	Please see Item Breakup for details.				116950.00	(-) 11.54	103453.97	
	Description:- SH:11.0 FLOORING							
11	Please see Item Breakup for details.				406325.00	(-) 11.54	359435.10	
	Description:- SH:12.0 ROOFING							

12	Please see Item Breakup for details.	1845755.15	(-) 11.54	1632755.01	
	Description:- SH:13.0 FINISHING				
13	Please see Item Breakup for details.	187675.00	(-) 11.54	166017.31	
	Description:- SH:14.0 REPAIRS TO BUILDING				
14	Please see Item Breakup for details.	21935.00	(-) 11.54	19403.70	
	Description:- SH:15.0 DISMANTLING AND DEMOLISHING				
15	Please see Item Breakup for details.	2161272.50	(-) 11.54	1911861.65	
	Description:- SH:16.0 ROAD WORK				
16	Please see Item Breakup for details.	704370.00	(-) 11.54	623085.70	
	Description:- SH:17.0 SANITARY INSTALLATIONS				
17	Please see Item Breakup for details.	516950.00	(-) 11.54	457293.97	
	Description:- SH:18.0 WATER SUPPLY				
18	Please see Item Breakup for details.	375537.50	(-) 11.54	332200.47	
	Description:- SH: 22.0 WATER PROOFING				

3. ITEM BREAKUP

Schedule	Schedule 01-All DSR ITEMS-2021 (Inclusive all taxes and GST @ 18%)					
Item- 01	SH: 0.1 HIRE CHARGES OF PLANTS & MACHINERY					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	0037	Mobile crane	Day	50.00	4500.00	225000.00
2	0039	Tractor with trolley	Day	100.00	1200.00	120000.00
3	0051	Hydraulic Excavator of 1 cum bucket	Hour	200.00	800.00	160000.00
					Total	**505000.00**
Item- 02	SH: 0.2 LABOUR					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	0111	Carpenter 1st class	Day	365.00	784.00	286160.00
2	0114	Beldar	Day	750.00	645.00	483750.00
3	0116	Fitter (grade 1) day	Day	250.00	784.00	196000.00
4	0123	Mason (brick layer) 1st class	Day	180.00	784.00	141120.00
5	0131	Painter	Day	50.00	714.00	35700.00
					Total	**1142730.00**
Item- 03	SH: 0.3 MATERIALS					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	0367	Portland Cement (OPC-43 Grade)	Tonne	50.00	5000.00	250000.00
2	0982	Coarse sand (zone III)	cum	208.00	1500.00	312000.00
3	1922	H.P. or L.P. ball valve with polythene floats: 15 mm dia	Each	100.00	215.00	21500.00
4	7261	C.P. Brass angle valve 15 mm	Each	200.00	350.00	70000.00
5	7400	15 mm PTMT bib cock	Each	300.00	65.00	19500.00
6	7406	PTMT pillar cock	Each	100.00	115.00	11500.00
7	7407	PTMT push cock 15 mm dia	Each	317.00	55.00	17435.00
					Total	**701935.00**
Item- 04	SH: 4.0 CONCRETE WORK					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	4.1.5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	10.00	6833.40	68334.00
					Total	**68334.00**
Item- 05	SH: 5.0 REINFORCED CEMENT CONCRETE					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**

1	5.2.2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	10.00	9861.70	98617.00
2	5.22A.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	1000.00	89.65	89650.00
					Total	**188267.00**

Item- 06	SH: 6.0 MASONRY WORK					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	6.1.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	35.00	6658.25	233038.75
2	6.4.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	70.00	8288.35	580184.50
					Total	**813223.25**

Item- 07	SH:8.0 CLADDING WORK					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	8.31	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	80.00	1063.45	85076.00
					Total	**85076.00**

Item- 08	SH: 9.0 WOOD AND P.V.C. WORK					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	9.83	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	Each	20.00	1025.65	20513.00
2	9.20.1	"Providing and fixing ISI marked flush door shutters conforming to IS :2202 (Part I) decorative type, core of block board construction withframe of 1st class hard wood and well matched teak 3 ply veneeringwith vertical grains or cross bands and face veneers on both faces ofshutters."35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	100.00	3086.10	308610.00
3	9.51.1	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete.With second class teak wood beading 62X19 mm	Sqm	100.00	1164.90	116490.00

4	9.120.1	"Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing."30 mm thick plain PVC door shutters	Sqm	50.00	2455.10	122755.00
5	9.7.7.2	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick :Float glass panes5.0 mm thick glass panes (weight not less than 12.50 kg/sqm).	Sqm	100.00	2231.20	223120.00
					Total	**791488.00**

Item- 09	SH 10: STEEL WORK					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	6000.00	111.95	671700.00
					Total	**671700.00**

Item- 10	SH:11.0 FLOORING					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	11.37	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	Sqm	125.00	935.60	116950.00
					Total	**116950.00**

Item- 11	SH:12.0 ROOFING					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**

1	12.50	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin- charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	500.00	671.55	335775.00
2	12.41.2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	Metre	200.00	319.75	63950.00
3	12.42.5.2	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conformingto IS : 13592 Type A, including jointing with seal ring conforming toIS : 5382, leaving 10 mm gap for thermal expansion.Bend 87.5°110 mm bend	Each	50.00	132.00	6600.00
					Total	**406325.00**

Item- 12	SH:13.0 FINISHING					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	13.4.1	12 mm cement plaster 1:4 (1 cement : 4 coarse sand)	Sqm	4000.00	307.25	1229000.00
2	13.81.1	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.One coat	Sqm	6257.00	54.75	342570.75
3	13.111.2	Finishing walls with Acrylic Smooth exterior paint of required shade :Old work (One or more coat applied @ 0.90 ltr/10 sqm).	Sqm	3000.00	72.70	218100.00
4	13.99.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm	648.00	86.55	56084.40
					Total	**1845755.15**

Item- 13	SH:14.0 REPAIRS TO BUILDING					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	14.76	"Cleaning and desilting of gully trap chamber, including removal ofrubbish mixed with earth etc. and disposal of same, all as per thedirection of Engineer-in-charge."	Each	500.00	89.45	44725.00

2	14.77	"Cleaning of chocked sewer line by diesel running vehicle mountinghydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. Dechocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150mm dia upto 300mm"	Metre	500.00	285.90	142950.00
					Total	**187675.00**
Item- 14	SH:15.0 DISMANTLING AND DEMOLISHING					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	15.60	Disposal of building rubbish/malba/similar unseviceale,dismantled or waste materials by mechanical means, including loading, transporting unloading to approved municipal dumping ground or as approved by Engineer - in-charge, beyond 50m initial lead, for all leads including all lifts involved.	cum	100.00	219.35	21935.00
					Total	**21935.00**
Item- 15	SH:16.0 ROAD WORK					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	16.4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density .	cum	200.00	865.80	173160.00
2	16.9	Scarifying metalled (water-bound) road surface including disposal of rubbish, lead upto 50 m and consolidation of the aggregate received from scarifying with power road roller of 8 to 10 tonne capacity.	Sqm	1000.00	27.55	27550.00
3	16.40	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum of fine aggregate per 100 sqm of road surface, including rolling and finishing with road roller all complete.	Sqm	1000.00	79.85	79850.00
4	16.77	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material within all lifts and lead upto 1km (by mechanical means).	Sqm	1000.00	5.85	5850.00
5	16.83	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	Sqm	500.00	108.65	54325.00
6	16.84	Laying old cement cocrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	Sqm	500.00	362.30	181150.00
7	16.3.2	Supplying and stacking at site.63 mm to 45 mm size stone aggregate	cum	50.00	1624.50	81225.00

8	16.3.3	Supplying and stacking at site. 53 mm to 22.4 mm size stone aggregate	cum	50.00	1837.25	91862.50
9	16.30.1	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications : On W.B.M. @ 0.75 Kg / sqm	Sqm	500.00	45.20	22600.00
10	16.30.2	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications :On bituminous surface @ 0.50 Kg / sqm	Sqm	500.00	36.60	18300.00
11	16.36.1	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy :For 50mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm.	Sqm	1000.00	414.20	414200.00
12	16.91.2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	Sqm	1000.00	1011.20	1011200.00
					Total	**2161272.50**

Item- 16	SH:17.0 SANITARY INSTALLATIONS					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	17.23	"Providing and fixing white vitreous china flat back or wall corner typelipped front urinal basin of 430x260x350 mm or 340x410x265 mmsizes respectively."	Each	50.00	1382.30	69115.00
2	17.2.1	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	Each	50.00	5540.55	277027.50

3	17.7.2	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:"White Vitreous China Wash basin size 630x450 mmwith a single 15 mm C.P. brass pillar tap"	Each	50.00	1913.75	95687.50
4	17.13.1	"Providing and fixing white vitreous china water closet squatting pan(Indian type) :"Long pattern W.C. pan of size 580 mm	Each	50.00	1667.80	83390.00
5	17.18.1	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 litre capacity - White	Each	100.00	1023.05	102305.00
6	17.20.1	"Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete :" White solid plastic seat with lid	Each	100.00	586.55	58655.00
7	17.28.1.1	"Providing and fixing P.V.C. waste pipe for sink or wash basin includingP.V.C. waste fittings complete."Semi rigid pipe32 mm dia	Each	200.00	90.95	18190.00
					Total	**704370.00**

Item- 17	SH:18.0 WATER SUPPLY					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Per Litre	20000.00	9.70	194000.00
2	18.9.2	"Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes,having thermal stability for hot & cold water supply including all CPVCplain & brass threaded fittings This includes jointing of pipes & fittingswith one step CPVC solvent cement, trenching, refilling & testing ofjoints complete as per direction of Engineer in Charge."20 mm nominal dia Pipes	Metre	500.00	275.25	137625.00
3	18.9.3	"Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes,having thermal stability for hot & cold water supply including all CPVCplain & brass threaded fittings This includes jointing of pipes & fittingswith one step CPVC solvent cement, trenching, refilling & testing ofjoints complete as per direction of Engineer in Charge."25 mm nominal dia Pipes	Metre	500.00	370.65	185325.00
					Total	**516950.00**

Item- 18	SH: 22.0 WATER PROOFING					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	22.14.1	Grading roof for water proofing treatment withCement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	cum	50.00	7510.75	375537.50
					Total	**375537.50**

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading

1	The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The Tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or One similar work each costing not less than the amount equal to 60% of advertised value of the tender. Similar nature for civil Engineering work is "Any civil work other than track work" is for technical experience/competence of advertised work in terms of Pr. Chief Engineer Circular No. 610 (Revised-3). As per the HQ/NDLS letter No. 74-W/0/Pt.XXV/Similar Nature of Works/WA dated 22-01-2020.	No	No	Allowed (Mandatory)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description

1	**Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.** Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. **(Click here** to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)
2	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/ We have visited the works site and I / We am / are aware of the site conditions.	No	No	Not Allowed

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	No post tender correspondence for submission of additional documents shall be entertained after opening ofthe Technical & Commercial offers. Even suo-moto post tender letters of the tenders shall be treated as NULL & Void.	Yes	No	Not Allowed
2	In case of other than Company/Proprietary firm, Annexure-XXIV-(A) shall also be submitted by each member of a Partnership firm /Joint venture (JV)/Hindu undivided Faimly(HUF) /Limited liability partnership (LLP) etc. as the case may be.	Yes	No	Allowed (Mandatory)
3	An Undertaking/Affidavit stating blacklisting status of Partners and Partnership firm (In case of Partnership firm, affidavit/undertaking must be signed by all the Partners) or Proprietor and proprietor firm or company and its constituents, Joint Venture and their constituents as per nature of firm to be upload by tenderer. An undertaking/affidavit regarding non blacklisting should be date of opening of bid to date of closing of bid.	Yes	No	Allowed (Mandatory)
4	The Tenderer should upload documentary proof regarding the nature and composition of firm as per Tender Document such as Partnership deed, Power of attorney if partnership firm / Affidavit if firm is Sole proprietor/MOU, Article of Association and Registration in companies act, if Registered company.	Yes	No	Allowed (Mandatory)
5	Power of attorney as per the tender form-3 (SECTION 4.4) to be uploaded in favour of the person signing the tender document.	Yes	No	Allowed (Mandatory)
6	Cover letter as provided in Tender Document (Section 4.2, Tender Form-1) required to be uploaded by the Tenderer on its letter head.	Yes	No	Allowed (Mandatory)
7	All financial documents required in Tender Document such as PAN card, GSTIN, Registration Certificates, Turnover certificate (Annexure-VII-B) duly certified by Chartered accountant, Certified copies of balance sheet etc required to be uploaded by the Tenderer.	Yes	No	Allowed (Mandatory)
8	General information of the Tenderer as provided in Tender Document (Section 4.3, Tender Form-2) to be uploaded by the Tenderer.	Yes	No	Allowed (Mandatory)

9	List of engineers/personnel already available/ proposed to be employed for deployment on this work, required to be uploaded by the Tenderer as per Annexure-X of Tender Document	Yes	No	Allowed (Optional)
10	Details of Plants and Machinery already available with the firm required to be uploaded by the Tenderer as per Annexure-IX of Tender Document.	Yes	No	Allowed (Optional)
11	Details of Electronic transfer of funds to the beneficiary as per the Annexure XII of the tender document.	Yes	No	Allowed (Mandatory)
12	Rate of inclusive of all taxes including GST@ 18%	Yes	No	Not Allowed
13	I/We have read and understood the tender document and all attached documents carefully. I abide by all the conditions specified in the Tender Document and all other attached documents.	Yes	No	Not Allowed
14	Any other document as required in the Tender Document or deemed fit by the Tenderer required to be uploaded.	Yes	No	Allowed (Optional)
15	Similar Nature of Work for this Tender is "Any civil work other than track work"	Yes	No	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	17-Sr-DEN-VI-LKO-2026-27.pdf	Tender Document

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: RANJEET

Designation : Sr.DEN-VI/LKO