Sr.DEN/CO-ORD/BZA acting for and on behalf of The President of India invites E-Tenders against Tender No **E-23-south-BZA-2026** Closing Date/Time 02/12/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	SW 1:NELLORE-vedayyapalem-Provision of IRS type shelter on eeach platform(ii)improvements to circulating ares BT surface in SSE/W/NLR section in ADEN/NLR subdivision.SW 2:Provision and Extension of COP on PF 4&5,2&3 and PF1 at KVZ station in SSE/W/KVZ section under ADEN/OGL sub division		
Bidding type	Normal Tender		
Tender Type	Open	**Bidding System**	Single Packet System
Tender Closing Date Time	02/12/2026 15:00	**Date Time Of Uploading Tender**	11/11/2026 15:38
Pre-Bid Conference Required	No	**Pre-Bid Conference Date Time**	Not Applicable
Advertised Value	57903854.46	**Tendering Section**	BUILDINGS
Bidding Style	Single Rate for Each Schedule	**Bidding Unit**	
Earnest Money (Rs.)	1158100.00	**Validity of Offer (Days)**	60
Tender Doc. Cost (Rs.)	0.00	**Period of Completion**	12 Months
Contract Type	Works - General	**Contract Category**	Expenditure
Bidding Start Date	18/11/2026		
Are JV allowed to bid	No	**Number of JV Member Allowed**	0
Are Consortium allowed to bid	No	**Number of Consortium Member Allowed**	0
Ranking Order For Bids	Lowest to Highest	**Expenditure Type**	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A1-Items in Schedule of Rates as per DSR-2023							3783970.76	Above/ Below/Par
1	Please see Item Breakup for details.				4451730.31	(-) 15.00	3783970.76	
	Description:- Items Covered Schedule of Rates as per DSR-2023							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A2-Items in Schedule of Rates as per DSR-2023							5942532.95	Above/ Below/Par
1	Please see Item Breakup for details.				6991215.24	(-) 15.00	5942532.95	
	Description:- Items in Schedule of Rates as per DSR-2023							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A3-Items in Schedule of Rates as per DSR-2023							382794.70	Above/ Below/Par
1	6.1.1	61.10	cum	7370.65	450346.71	(-) 15.00	382794.70	
	Description:- MASONRY WORK // General // Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: // Cement mortar 1:4 (1 cement : 4 coarse sand)							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit

Schedule () A4-Items in Schedule of Rates as per DSR-2023							5798150.32	Above/ Below/P ar
1	Please see Item Breakup for details.				6821353.32	(-) 15.00	5798150.32	
	Description:- Items in Schedule of Rates as per DSR-2023							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A5-Items in Schedule of Rates as per DSR-2023							2272859.21	Above/ Below/P ar
1	5.22A.6	24793.25	Kg	107.85	2673952.01	(-) 15.00	2272859.21	
	Description:- REINFORCEMENT CEMENT CONCRETE // STEEL REINFORCEMENT // Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. // Thermo-Mechanically Treated bars of grade Fe-500D or more.							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A6-Items in Schedule of Rates as per DSR-2023							38789895.74	Above/ Below/P ar
1	Please see Item Breakup for details.				45635171.46	(-) 15.00	38789895.74	
	Description:- Items in Schedule of Rates as per DSR-2023							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A7-Schedule of rates not Covered in DSR-2023 & USSR 2021							933650.78	Above/ Below/P ar
1	Please see Item Breakup for details.				933650.78	AT Par	933650.78	
	Description:- Items not covered in Schedule of Rates as per DSR-2023 & USSR 2021							

3. ITEM BREAKUP

Schedule	Schedule A1-Items in Schedule of Rates as per DSR-2023						
Item- 1	Items Covered Schedule of Rates as per DSR-2023						
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**	
	2.0	EARTH WORK					
	2.1S	General					
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge.					
1	2.6.1	All kinds of soil	cum	1744	177.5	309560	
	2.20	Open timbering in trenches including strutting and shoring complete (measurements to be taken of the face area timbered):					
2	2.20.2	Depth exceeding 1.5 m but not exceeding 3 m	Sqm	932.3	81.6	76075.68	
3	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	cum	1349.14	196	264431.44	

4	2.25A	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	cum	650	700.5	455325
	2.26	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials.				
5	2.26.1	All kinds of soil	cum	564.2	126.8	71540.56
6	2.27	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	cum	155.42	2123.75	330073.23
	15.0	DISMANTLING AND DEMOLISHING				
	15.1S	General				
7	15.59	Dismantling of flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material up to a lead of 1kilometre, as per direction of Engineer-in-charge.	cum	18	420.8	7574.4
	16.0	ROAD WORK				
	16.30S	PREMIX CARPET				
	16.31	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributer including preparing the surface & cleaning with mechanical broom.				
	16.31.1	With rapid setting bitumen emulsion				
8	16.31.1.2	On bituminous surface @ 0.25kg/sqm	Sqm	4500	9.2	41400
	16.36	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy :				
9	16.36.1	For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm.	Sqm	4500	505.65	2275425
	16.40S	SEAL COAT				
10	16.41	Providing and laying seal coat over prepared surface of road with bitumen heated in bitumen boiler fitted with the spray set spraying using 98 kg of bitumen of grade VG - 10 and blinding surface with 0.90 cum of stone aggregate of 6.7 mm size (Passing 11.2 mm sieve and retained on 2.36 mm sieve) per 100 sqm of road surface, including rolling and finishing with power road roller all complete..	Sqm	4500	130.85	588825
	16.49S	MISCELLANEOUS				
11	16.77	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material within all lifts and lead upto 1km (by mechanical means).	Sqm	4500	7	31500

					Total	**4451730.31**
Schedule	Schedule A2-Items in Schedule of Rates as per DSR-2023					
Item- 1	Items in Schedule of Rates as per DSR-2023					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
	4.0	CONCRETE WORK				
	4.1S	CEMENT CONCRETE (CAST IN SITU)				
	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
1	4.1.6	1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal size derived from natural sources)	cum	102.08	7178.75	732806.8
	5.0	REINFORCEMENT CEMENT CONCRETE				
	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
2	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	699.6	392.15	274348.14
	5.12S	PRE-CAST RCC				
3	5.12	Providing, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but , excluding cost of reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	cum	16.65	10585.9	176255.24
	5.33S	DESIGN MIX CONCRETE				
	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge, for the following grades of concrete.:				
	5.33.1	All works upto plinth level				
4	5.33.1.2	Concrete of M30 grade with minimum cement content of 350 kg /cum	cum	472.33	9655.7	4560676.78
5	5.35	Add for using extra cement in the items of design mix over and above the specified cement content therein.	Quintal	39.76	733.5	29163.96
	15.0	DISMANTLING AND DEMOLISHING				
	15.1S	General				
	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
6	15.2.1	Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	cum	179.51	2434.25	436972.22

	16.0	ROAD WORK				
	16.49S	MISCELLANEOUS				
7	16.75	Providing and laying C.C. pavement of mix M-25 with ready mixed concrete from batching plant. The ready mixed concrete shall be laid and finished with screed board vibrator , vacuum dewatering process and finally finished by floating, brooming with wire brush etc. complete as per specifications and directions of Engineer-in-charge. (The panel shuttering work shall be paid for separately).	cum	79.5	9823.8	780992.1
					Total	**6991215.24**
Schedule	Schedule A4-Items in Schedule of Rates as per DSR-2023					
Item- 1	Items in Schedule of Rates as per DSR-2023					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
	1.0	CARRIAGE OF MATERIALS				
	1.1	By Mechanical Transport including loading, unloading and stacking				
1	1.1.18	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.	cum	1406.14	494.1	694773.77
	8.0	CLADDING WORK				
	8.1S	General				
	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels				
	8.2.2	Granite stone slab colour black, Cherry/Ruby red				
2	8.2.2.2	Area of slab over 0.50 sqm	Sqm	605.9	5136.3	3112084.17
	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.				
3	8.3.2	Granite work	Metre	350	510.95	178832.5
	12.0	ROOFING				
	12.37S	RAIN WATER SPOUT AND PIPE				
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
4	12.41.2	110 mm diameter	Metre	735.29	377.4	277498.45

	12.66	Providing and fixing of Pre-coated colour or mill finish Aluminium Roofing Accessories in 0.71 mm thickness ,Alloy 31500 (IS designation) [Aluminium Alloy (AA) 3004 (ISO designation)] For colour, coating shall be 5-7 microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns, using self drilling/tapping SS screws of size 6 x 50 mm with 3 mm thick EPDM seal and SS plain washer complete :				
5	12.66.6	Precoated/mill finish aluminium Gutter (600 mm over all girth)	Metre	813.6	1808.65	1471517.64
	13.0	FINISHING				
	13.1S	CEMENT PLASTER (IN FINE SAND)				
	13.2	15 mm cement plaster on the rough side of single or half brick wall of mix :				
6	13.2.1	1:4 (1 cement: 4 fine sand)	Sqm	189.3	399.45	75615.89
	13.44S	EXTERIOR FINISHING				
	13.63	Painting with aluminium paint of approved brand and manufacture to give an even shade .				
7	13.63.1	Two or more coats on new work	Sqm	5466.75	146.8	802518.9
	13.100	Painting with aluminium paint of approved brand and manufacture to give an even shade:				
8	13.100.1	One or more coats on old work	Sqm	2172	96	208512
					Total	**6821353.32**

Schedule	Schedule A6-Items in Schedule of Rates as per DSR-2023
Item- 1	Items in Schedule of Rates as per DSR-2023

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	10.0	STEEL WORK				
	10.1S	General				
1	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	256730.96	133.7	34324929.35
2	10.19	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	Kg	30204.14	97.2	2935842.41
3	10.20	Providing and fixing bolts including nuts and washers complete.	Kg	3110.4	159.35	495642.24
	12.0	ROOFING				
	12.1S	SHEET ROOFING				
	12.5	Providing valleys of 90 cm wide overall in plain G.S. sheet fixed with polymer coated J, or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete :				
4	12.5.1	1.60 mm thick with zinc coating not less than 350 gm/m2	Metre	798.45	1863.9	1488230.96
	12.37S	RAIN WATER SPOUT AND PIPE				

5	12.50	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05 mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	8651.63	738.65	6390526.5
					Total	**45635171.46**

Schedule	Schedule A7-Schedule of rates not Covered in DSR-2023 & USSR 2021					
Item- 1	Items not covered in Schedule of Rates as per DSR-2023 & USSR 2021					
S No.	**Item No**	**Description of Item**	**Unit**	**Qty**	**Rate**	**Amount**
1	1	Repairs to opening of cover over platforms around OHE masts portals using resin and glass fibre treatment by covering the gap with resin and glass fibre in two coats of total layers of 2.0 to 2.5 mm thickness including preparing the existing surface by wire brushes and cleaning and covering the gap for water tight including testing with all contractor men, materials, tools, plants, including transportation of materials to the site with inclusive of taxes, scaffolding, crossing of track wherever necessary etc., complete as directed by the Engineer-in-charge at site. Note: Any wide gaps shall be covered with galvalume sheet pieces provided by Railway duly treating the whole area with Glass fibre treatment(Rate is arrived as per approved rate analasis vetted by Sr.DFM/SC vide Lr.No.No.AFX-I/Central/Misc-46/2024 ,Dt: 07.08.2024.)	Sqm	118.00	1629.20	192245.60
2	2	Repairs to valley Gutter joints of GI/AC/Galvalume by using resin and glass fibre treatment, by preparing the surface removing the existing treatment scarping the surface by wire brush, applying the resin and glass fibre in two layers ie, 1.5 to 2.0 mm thickness, 10 cm width to cover the crack including testing joints with all contractor men, materials, tools, plants, including transportation of materials to the site with inclusive of taxes, scaffolding, crossing of track wherever necessary etc., complete as directed by the Engineer-in-charge at site.(Rate is arrived as per approved rate analasis vetted by Sr.DFM/SC vide Lr.No.No.AFX-I/Central/Misc-46/2024 ,Dt: 07.08.2024.)	Metre	1360.00	400.44	544598.40

3	3	Repairs to Holes of size upto 15 Cm x 15 Cm patch work in GI AC/Galvalume roofing's by using resin and glass fibre by preparing the surface removing the existing treatment and scraping the surface by wire brush applying the resin and glass fibre in 2 layers of 1.5 to 2 mm thickness including testing the joints with all contractor men, materials, tools, plants, including transportation of materials to the site with inclusive of taxes, scaffolding, crossing of track wherever necessary etc., complete as directed by the Engineer-in- charge at site. (Rate is arrived as per approved rate analasis vetted by Sr.DFM/SC vide Lr.No.No.AFX-I/Central/Misc-46/2024 ,Dt: 07.08.2024.)	Numbers	843.00	233.46	196806.78
					Total	**933650.78**

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Financial Eligibility Criteria: as per Clause 10.2 ofPart-I of IRSGCC-2022and as per Railway BoardAdvance correction slip No.1 dated 14-07-2022Thetenderer must have minimum average annualcontractualturnoverof V/N or "V" which ever is less:where V= Advertised value ofthe tenderin crores ofRupees N= Number of years prescribedforcompletion ofwork for which bids have been invited.The averageannual contractualturnover shall becalculated as an average of"totalcontractualpayments" in the previous threefinancial years, as perthe auditedbalance sheet.However, in case balance sheet of the previousyearisyet to be prepared/ audited, the audited balancesheet of thefourthprevious year shall be consideredfor calculating averageannualcontractual turnover.The tenderers shall submit requisiteinformationasper Annexure-F (Annexure-VIB of GCC), alongwith copies ofAuditedBalance Sheets duly certifiedby the Chartered Accountant/CertificatefromChartered Accountant duly supported by AuditedBalanceSheet	No	No	Allowed (Mandatory)
1.1	Financial Eligibility Criteria: As per Clause 10.2 ofIRSGCC-2022 (AsperAdvanced Correction slip No,1dated. 14.07.2022 to GCC-2022) andthesame ismentioned in para no.10.2 page no. 15 of thistenderdocument.Tenderer should attach Selfattested/Digitally signed copy ofCertificateshowingminimum average annual contractual turnover asperAnnexureVIB of IRSGCC-2022 (As per AdvancedCorrection slip No,1dated.14.07.2022 to GCC-2022)in Annexure - "F"Page-32 of MasterDocument -1attached to the tender	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	B.V. b): Any work consisting of steel fabrication and erection of FOB or Steel/Composite girder Bridges or ROB with Steel Composite girder Or Industrial Shed or PF Shelter (steel) or Microwave/HT Tower or Replacement of steel members/repairs on steel girder Bridges or Steel Sleepers over girder Bridges vide CGE Lr. No. W.148/P/SNW/2025 Dt.02.12.2025 with the approval of PCE.	No	No	Allowed (Mandatory)
1.1	Technical Eligibility Criteria: as per Clause 10.1 ofPart-I of IRSGCC-2022(a) The tenderer must havesuccessfully completed orsubstantiallycompletedany one of the following categories ofwork(s)during last 07(seven) years, ending last day ofmonth previous tothe one in whichtender is invited:(i) Three similar works each costing notless thantheamount equal to 30% of advertised value of thetender, or (ii)Two similarworks each costing notless than the amount equal to 40%ofadvertisedvalue of the tender, or (iii) One similarwork costing not lessthan theamount equal to 60%of advertised value of the tender	No	No	Allowed (Mandatory)

1.1.1	(b) (1) In case of tenders for composite works (e.g.works involvingmorethan one distinct component,such as Civil Engineering works,S&Tworks,Electrical works, OHE works etc. and in the case ofElectricalworks, OHE works etc. and in the case ofmajor bridges - substructure,superstructure etc.),tenderer must have successfullycompletedorsubstantially completed any one of the followingcategoriesof work(s)during last 07 (seven) years,ending last day of monthprevious to the oneinwhich tender is invited: (i) Three similar workseachcosting not lessthan the amount equal to 30% ofadvertised valueof each component oftender, or (ii)Two similar works each costing notless than theamountequal to 40% of advertised value ofeachcomponent of tender, or (iii) Onesimilar workeach costing not less thanthe amount equal to 60%ofadvertised value of each component oftender.Note for b(1): Separatecompleted works ofminimum requiredvalues shall also be consideredforfulfilment of technical eligibilitycriteria fordifferent components. (b)(2) Insuch cases, whatconstitutes acomponent in a composite work shallbeclearly pre-defined withestimated tender cost ofit, as part of the tenderdocuments withoutanyambiguity. (b) (3) To evaluate thetechnicaleligibility of tenderer, onlycomponents of work asstipulated intender documents for evaluationoftechnical eligibility, shall beconsidered. Thescope of work covered inother remainingcomponentsshall be either executed bytendererhimself if he has work experienceasmentioned in clause 7 of theStandard GeneralConditions of Contractorthroughsubcontractorfulfilling the requirements as perclause 7 of theStandard GeneralConditions ofContract or jointly i.e., partly himselfandremainingthrough subcontractor, with priorapproval of ChiefEngineer in writing.However, ifrequired in tender documents by way ofSpecialConditions, aformal agreement duly notarised,legally enforceablein the court of law,shall beexecuted by the main contractor withthesubcontractor for thecomponent(s) of workproposed to be executedby thesubcontractor(s),and shall be submitted along withthe offer forconsidering subletting ofthat scope ofwork towards fulfilment of technicaleligibility.Suchsubcontractor must fulfill technical eligibilitycriteria asfollows: Thesubcontractor shall havesuccessfully completed at least oneworksimilar towork proposed for subcontract, costing not lessthan35%value of work to be subletted, in last 5years, ending last day ofmonthprevious to the onein which tender is invited through aworkscontract.Note: for subletting of work costing up toRs 50 lakh, noprevious workexperience ofsubcontractor shall be asked for by theRailway. Incaseafter award of contract or during execution ofwork itbecomes necessaryfor contractor to changesubcontractor, the same shallbe donewithsubcontractor(s) fulfilling the requirements asper clause 7 oftheStandard General Conditions ofContract, with prior approval ofChiefEngineer inwriting	No	No	Allowed (Optional)
1.1.2	Note for Item 10.1 of IRSGCC-2022: Workexperience certificatefromprivate individual shallnot be considered. However, in additiontoworkexperience certificates issued by any Govt.Organization,workexperience certificate issued byPublic listed company havingaverageannualturnover of Rs 500 crore and above in last 3financialyearsexcluding the current financial year,listed on National StockExchange orBombay StockExchange, incorporated/registered at least 5yearsprior tothe date of closing of tender, shall also beconsideredprovided the workexperience certificatehas been issued by a personauthorized bythePublic listed company to issue such certificates.In casetenderer submitswork experience certificateissued by public listedcompany, the tenderershallalso submit along with work experiencecertificate,the relevantcopy of work order, bill of quantities,bill wisedetails of paymentreceived duly certifiedby Chartered Accountant, TDScertificates forallpayments received and copy of final/last bill paidbycompany in supportof above work experiencecertificate	No	No	Allowed (Optional)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.

3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	**Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.** Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. **(Click here** to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local contentin the materialbeingoffered. Please enter 0for fully imported items, and 100forfullyindigenous items. The definition andcalculation oflocalcontent shall be inaccordance with the Make in Indiapolicyasincorporated in the tender conditions	No	No	Allowed (Optional)
2	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Tender value is including escalation of (-)15% (minusfifteenpercent) on CPWD DSRrates. Tenderer should notethisbeforequoting the rates	No	No	Not Allowed
2	The original Bank Guarantee (in lieu of BidSecurity) shouldbedelivered in person to theofficial nominated(i.e.OS/Tenders/Engg)/BZADivision) as indicated in thetenderdocumentbefore closing date for submission ofbids(i.e.excluding the last date of submission ofBids)	No	No	Not Allowed

3	All the instructions furnished in the TechnicalCompliance/Commercial Compliance /Custom / Undertakings /GeneralInstructionsare only indicative and not exhaustive.Thetenderershall read the GCC / Tenderdocuments for completedetails	No	No	Not Allowed
4	The tenderer shall thoroughly go through theentiretenderdocument and strictly adhere tothe instruction anddirectionsgiven therein	No	No	Not Allowed

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	List of personnel organizations available onhand and proposedtobe engaged for thesubject work. These two lists shouldbegivenseparately and singed by tenderer and aretobesubmitted in the proforma in theAnnexure - "A"	No	No	Allowed (Optional)
2	List of Plants & Machinery available on hand(own) andproposedto be included (own &hired to be given separately) forthesubjectwork and this list shall be signed by thetenderer andisto be submitted in proformagiven in the Annexure - "B"	No	No	Allowed (Optional)
3	List of completed works in the last threeFinancial Yearsgivingdescription of work,organisation forwhomexecuted,approximate value of contract atthe time ofaward, date ofawarded and dateof scheduled completion ofwork, dateofactual start, actual completion and finalvalue ofcontract shouldalso be given in theAnnexure - "C"	No	No	Allowed (Optional)
4	List of on hand indicating name of work,contract value,billamount paid so far, duedate of completion etc., to befurnishedbythe tenderer in the Annexure - "D" andcertificate tobesigned by tenderer	No	No	Allowed (Optional)
5	Tenderer should submit attested copy ofExperience CertificateinAnnexure-E. (Bidderwho does not enclosetheExperienceCertificate, his/their bid shall besummarilyrejected). Note:Applicable for thetenders floated value aboveRs.50 lakhs	No	No	Allowed (Mandatory)
6	Tenderer should submit annual contractualTurnoverCertificateAnnexure-VIB as perpara 10.2 of Part-I, GCC-2022.(Bidderwhodoes not enclose the TurnoverCertificate, his/theirbid shall besummarilyrejected). Note: Applicable for thetendersfloatedvalue above Rs.50 lakhs.	No	No	Allowed (Mandatory)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/ We have visited the works site and I / We am / are aware of the site conditions.	No	No	Not Allowed
2	I/ We have visited the works site and I / We am / are aware ofthe site conditions	No	No	Not Allowed

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderers in their bids shall indicate thedetails oftheirJurisdictional Assessing officer(Designation, Address and e-Mailld).In caseof contract awarded, a copy ofLAO/PurchaseOrdershall be immediately forwardedbypurchaser/Executive to theJurisdictionalAssessing officermentioned in the tenderer'sbid.(GST)	No	No	Allowed (Mandatory)

2	The tenderer shall clearly specify whetherthe tender issubmittedon his own(Proprietary Firm) or on behalf ofaPartnership Firm /Company / Joint Venture(JV) / RegisteredSociety / RegisteredTrust /HUF etc. The tenderer(s) shallenclose theattested copiesof the constitution of theirconcern,and copy of PAN Card alongwiththeir tender. TenderDocuments in suchcases are to besigned by such personsasmay be legally competent to sign themonbehalf of the firm,company, association,trust or society, as thecase may be.Pleaseread carefully (provision of Para-14 ofGCC)the documentrequired to be uploaded here	No	No	Allowed (Mandatory)
3	Any other information / Certificates / GeneralPower ofAttorneyrequired as per Tender forPartnership Firms, Company;Thetendererwhether sole proprietor / a company orpartnershipfir /registered society /registered trust / HUF / LLP etc., iftheywantto act through agent or individualpartner(s), shouldsubmitalong with thetender, a copy of power of attorneydulystampedand authenticated by a NotaryPublic or byMagistrate in favourof thespecific person whether he/theybepartner(s) of the firmor any other person,specificallyauthorizing him/them to signthetender, submit the tender andfurther to dealwith theTender/ Contract up to the stage ofsigningthe agreementexcept in case wheresuch specific person isauthorized forabovepurposes through a provision made inthepartnershipdeed/ Memorandum ofUnderstanding / Article ofAssociation/Boardresolution, failing which tender shallbesummarilyrejected. Note: Please readcarefully (provisions ofPara-15 ofGCC) thedocument required to be uploaded here	No	No	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	masterdocument1aug2026.pdf	Master Document 1
2	masterdocument2aug2026.pdf	Master Document 2
3	Buidingconditionsn23.pdf	building conditions
4	CEWorksSiterecords26.05.2022.pdf	ce works site records
5	DESIGNMIXHQrsLETTERONSPECIALCONDITIONSFORDESIGNMIX2123-03-20225.pdf	design mix
6	EARTHWORKCONDITIONS23.pdf	Earth work conditions
7	GENERALCONDITIONS23.pdf	general conditions
8	RevisedBrands26022026.pdf	revised approved
9	SAFETYPRECAUTIO.23.pdf	safety precautions
10	SitelaboratoryestablishmentHQrsletter.pdf	site laboratory
11	SpecialConditionsforDrawings23.pdf	special conditions for drawing 14
12	SPECIFICATIONSOFCONTROLLEDCONCRETE23.pdf	specifications for concrete
13	SPECIFICATIONSFORROOFINGGALVALUMESHEETS..pdf	special conditions
14	STEELSPECIALCONDITIONS23.pdf	steel conditions
15	TRDsafetyconditions23.pdf	trd conditions

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: KOTIPALLI DURGA SAIKRISHNA

Designation : Sr.DEN/S/BZA